ENGINEERING DEPARTMENT

BEREAU OF SANITARY ENGINEERING, BANGALORE.

Notice dated 10th February 1937.

The attention of the public is invited to the Notification, dated 6th February 1937, calling for tenders for the work of " Providing sanitary fittings to the lavatories at the New Telephone Exchange Building ", published in pages 220-221, Part VI of the *Mysore Gazette*, dated 18th February 1937.

The last date of receiving the tenders is fixed on 26th February 1937.

Notice dated 13th February 1937.

The attention of the public is invited to the Notification, dated 10th February 1937, calling for tenders for the work of " Providing sanitary fittings to the Central College House at Bangalore", published in pages 221-223, Part VI of the *Mysore Gazette*, dated 18th February 1937.

The last date of receiving the tenders is fixed on 8th March 1937.

Notification dated 17th February 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 15th March 1937, for the work of providing sanitary installation in New Railway Offices at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 120 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for the work of providing sanitary installation in New Railway Offices at Mysore," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Approximate estimate of quantities for providing sanitary installation in the New Railway Offices, Mysore.

No.	Particulars	Unit	Quantity
	Labour for Sanitary Fittings.		
1	Fixing water closets, lavatory and urinals set	No.	28
2	Fixing accessories	„	20

No.	Particulars	Unit	Quantity
3	Providing 4″ C.I. soil pipes with specials such as bends, off-sets and junctions, etc., laying and jointing with lead including wall, terrace and cornice bore, wall, terrace and stonewall grooving and redoing with cement earthwork excavation, refilling, cutting floor and redoing with tiles, etc., including scaffolding and providing 4″ zinc cowls, etc., complete and fixing with screens and wooden plugs to walls	R.ft.	320
4	Do 3″ do	,,	200
5	Providing and fixing 2″ lead pipes with wiped solder joints including providing and fixing brass thimbles and tails wherever necessary as per above	,,	100
6	Providing 4″ lead pipes bending and fixing with wiped solder joints including providing and fixing 4″ brass thimbles and tails ..	No.	12
7	Providing 1½″ lead pipe bending and fixing with wiped solder joints, etc., for waste pipes	,,	8
8	Do ¾″ and ½″ for water connection and overflow ..	,,	48
9	Providing and fixing ½″ N.P. stop cocks with unions	,,	24
10	Do bib cocks	,,	4
11	Providing and fixing 6″×3″ C. I. trap including constructing cement concrete cistern and providing 6″ dia. N.P. grating	,,	8
12	Cutting floor and filling cement concrete alround the *pan* and trap including below the trap 6″ deep and earthwork excavation, etc., complete	,,	4
13	Painting sanitary fittings and pipes, etc., in 3 coats white enamel paint	,,	24
14	Water connections :— Providing 1½″, 1″, ¾″ and ½″ galvanised pipes with fittings including laying and jointing and cutting and threading and wall cornice and terrace bore of walls, cornice and terrace grooving and redoing earthwork excavation and refilling and tamping and cost of gland cock and gland cock cistern with cost of road box and fixing, etc., complete 1½″	R.ft.	500
15	Do do 1″ do	,,	200
16	Do do ¾″ and ½″ do	,,	300
17	Boring hole in water pipe C. I. main line including earthwork excavation and refilling, tamping 1½″ bore and fixing bend and gland cock and constructing cistern and cost of road box and finishing, etc., complete	No.	1
	Drainage Arrangements.		
18	Providing 6″ stoneware pipe of best quality, laying and jointing in cement mortar, earthwork excavation in hard and soft soil or hard or soft rock and refilling, watering and tamping complete with removal of surplus earth and forming and cleaning, etc., complete including all charges, of testing	R.ft.	370
19	Do 4″ do	,,	80
20	Providing and fixing 6″×4″ stoneware gully trap with grating including constructing cistern in cement mortar and providing and fixing hinged lid and frame C. I. and painting, etc., complete	No.	2
21	Constructing circular manhole of 4′ dia. inside upto 6′ depth earthwork excavation cement concrete bed 1′ depth with 3″ projection and side walls brick in cement mortar 9″ thick walls alround cement plastering, making drain in cement concrete providing and fixing 21″ dia. C.I. manhole cover and frame of 2 cwt., including removal of surplus earth and site clearing, etc., complete	,,	3
22	Providing 6″ dia. C. I. hydraulic pipe, laying and jointing with lead including boring hole in stonewall and redoing with cement and earthwork excavation and refilling and tamping and removing surplus earth, etc., complete	R.ft.	72

No.	Particulars	Unit	Quantity
23	Boring hole in existing manhole and redoing same with cement mortar and making drain, etc., complete	No.	1
24	Repairing road crossing with extra metal	R.ft.	66

Notification dated 21st February 1937.

The attention of the public is invited to Notification of tender, dated 30th January 1937, printed on page 193, Part VI of the *Mysore Gazette*, dated 11th February 1937, calling for tenders for the Tumkur drainage scheme.

In modification of clause No. 4, requiring a deposit of Rs. 7,735 along with the tender application, the following rule will be observed :—

1. An earnest money of Rs. 500 should be deposited along with the application. On approval of any particular tender, the accepted tenderer should deposit the balance amount at 5 per cent of the total estimated value.

B. R. GARUDACHAR,
Sanitary Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Notice dated 10th February 1937.

It is hereby notified that about 3,000 empty Alum Bags will be auctioned at the Workshop premises of Chamaraj Sagar and Water Works, Thippagondanhalli, on 1st March 1937 between 9 A.M. and 12 NOON. Intending purchasers may attend the auction on 1st March 1937. The full amount of the bid will have to be credited by the successful bidder at the Chamaraja Sagar and Water Works Sub-Division Office before the bags are removed. All the bags must be removed within three days from the date of auction.

Abtract Notification, dated 9th February 1937.

The attention of the public is invited to the *Mysore Gazette* Notification dated 9th February 1937, calling for tenders for the work of Water Supply to the New Mental Hospital. The last date of receipt of tenders is 8th March 1937. Earnest money to be deposited is Rs. 150.

V. GANESHA IYER,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 8th February 1937.

The attention of the public is invited to the Notification on pages 210-211, Part VI of the issue of *Mysore Gazette*, dated 11th February 1937, calling for tenders for the work of constructing Combined Range Officer's Quarters and Office at Malur.

The last date fixed for the receipt of tenders in this office is 2 P.M., on 2nd March 1937.

An earnest money of Rs. 150 should accompany each tender.

Abstract Notification dated 10th February 1937.

The attention of the public is invited to the Notification published in pages 225-226, Part VI of the issue of *Mysore Gazette*, dated 18th February 1937, calling for tenders for the work of Restoring Mirapalli Chinnapothalaiyanakunte, Minor tank, Mittemari hobli, Reg. No. 412, Bagepalli Taluk.

The last date fixed for the receipt of tenders in this office is 2 P.M. on 10th March 1937.

P. RAJAGOPALAN,
Executive Engineer.